Approximate estimate of quantities of work for extending the Pump House at Harihar for Davangere Water Works.

No.	Particulars	Unit	Quantity
1	Earthwork excavation and filling in the basement	C.yd.	47
2	Stone jelly concrete in chunam mortar	C.ft.	785
3	Burnt stone in chunam mortar for foundation and basement ..	,,	724
4	Burnt brick in chunam mortar	,,	1,499
5	Burnt stone slabs dressed and fixed 6″ thick	S.ft.	561
6	Plastering with chunam mortar ½″ thick	,,	23.62
7	Cement pointing to basement	,,	1.61
8	Rolled steel beams including hositing and fixing, etc., complete	Cwt.	60
9	Roofing with jack arched terrace	Sqr.	8.58
10	Teakwood door of 3½″×4½″ frame with pannelled shutters 1¼″ thick including iron fittings, etc., complete ..	S.ft.	72
11	Teakwood windows with half pannelled and half glazed shutters including iron fittings, etc., complete	,,	84
12	Do removing and refixing	Each	4
13	Teakwood ventilators with glazed shutters including iron fittings, etc., complete	S.ft.	27
14	Removing and refixing ventilators	Each	4
15	Painting with grey silicate paint, 2 coats	Sqr.	25.00
16	Cornice 9″ thick with burnt brick in chunam mortar including plastering with chunam	R.ft.	80
17	Parapet wall 2 ft. high with burnt brick in mortar and plastering with chunam as per design	R.ft.	80
18	Cutting quoins at corners	Sqr.	1.28
19	Flooring with 3″ stone jelly concrete and 1″ cement concrete with cement plastering complete	,,	6.92

B. R. GARUDACHAR,
Sanitary Engineer.

BANGALORE DIVISION.

Notification dated 4th November 1936.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Bangalore Division, up to 2 P.M. on 23rd November 1936, for the maintenance work to Mankunda, Major Tank Registered No. 103 of Channapatna Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of May 1937.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Bangalore between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees one hundred only in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for the maintenance work to Mankunda Major Tank, Register No. 163 of Channapatna Taluk" in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for Contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

Approximate quantities required for the maintenance work to Mankunda Major Tank, Register No. 103 of Channapatna Taluk.

No.	Items of work	Unit	Quantity	Rate sanctioned	Rate quoted in	
					Words	Figures
				Rs. a. p.		
1	Earthwork to bund with the required lead and lift including watering and tamping	C.yd.	1,503	0 4 0		
2	Clearing jungle and cutting grips ..	Grade	25	2 0 0		
3	Turfing the slopes of bund and watering till it is satisfactory ..	S.yd.	8,721	0 1 0		
4	Providing and fixing new grade stones with figure and cut painted and numbered	Each	6	1 8 0		
5	Cutting figures to grade stones painting and numbering	,,	29	0 5 0		
6	Providing and fixing new B. M. stones with figures cut painted and numbered	,,	2	2 0 0		
7	Do Register No. stone do	,,	1	2 12 0		
8	Do gauge stone do	,,	1	10 0 0		

N. SUBBA RAO,
Executive Engineer.

MYSORE DIVISION.

Abstract Notification dated 24th October 1936.

The attention of the public is hereby invited to the advertisement published on pages 1821-1822 of the *Mysore Gazette*, dated 5th November 1936, Part VI, calling for tenders for the construction of a Girder Bridge with well curbs, foundations, piers and abutments across River Shimsha, at Halagur 2/55 of Bangalore-Mysore Road *via* Kankanhalli.

The last date of receipt of tender is 18th November 1936.

V. V. PATANKAR,
Executive Engineer.

SHIMOGA DIVISION.

Notification dated 5th November 1936.

The following unserviceable articles will be disposed of by public auction at the premises of the office of the Executive Engineer, Shimoga Division, Shimoga, at 9 A.M. on 13th December 1936.

1. The officer conducting the auction does not bind himself to accept the highest bid or any bid at all and it is open to him to cancel the auction for reasons found sufficient by him.

2. The highest bidder whose bid is accepted should pay 25 per cent of the bid amount on the spot and the rest before removing the articles.